BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35698

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2019-20, Date: 14.05.2019

Desilting of Drains in ward 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )	
				In Figures	In Words
1	10845	Removing and Refixing stone slabs of drains and pointing in C.M(1:3)1	Sqm	94.6	Rupees Ninety Four and Sixty Paise Only
2	2488.13	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications..	cum	117.15	Rupees One Hundred Seventeen and Fifteen Paise Only
3	2488.13	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	80.16	Rupees Eighty and Sixteen Paise Only

U Ramesh

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

4/07